

The PFT-401CEF is a CE Marked AC Dielectric Test Set, one of many in the PFT **Series** of field portable AC hipot test sets. These hipots provide continuously adjustable AC voltage typically used to provide a go/no-g o, or pass/fail, AC over-voltage Withstand Test on high voltage apparatus, like switchgear, circuit breakers, reclosers, vacuum bottles, hot sticks, bus duct, and any other equipment needing an AC voltage proof test. The PFT Series offers the most field portable, affordable, and easiest to use AC testers at this voltage and power. Please see our higher voltage and kVA rated HPA and PAR lines for component testing and larger loads such as motors, generators, and substation apparatus. These other lines offer corona free output for Partial Discharge and Tan Delta testing. Some are CE Certified like this model.

- Split case design: Single piece for storage, separates for safe operation
- Digital Volt & Current meters, memory voltmeter displays fault voltage
- Guard/Ground circuit for accurate leakage current measurement
- Adjustable overload circuit from 10-110% of rated output current
- Primary current overload w/backup breaker protection
- Zero Start and External safety Interlock provisions
- · Keyed Main Power switch

Model	PFT - 401CEF
Input	230Vac, 50/60Hz, 6A
Output	0-40kV AC, 1kVA resistive load (25mA Max) 1kVA capacitive load (25mA max)
Duty	1kVA: 1 hour ON, 1 hour OFF 0.8kVA: continuous
Distortion	Less than 5%
Meter Accuracy	1%
Voltmeter	3.5" digital LED, scaled 0-40kV AC (RMS)
Current Meter	3.5 digit LED, scaled 0-25ma AC (RMS)
Size & Weight (W x D x H)	14.5 x 12.5 x 23.5 in., 70 lb 368 x 318 x 597 mm, 32 kg HV Section: 35lb (16kg) Control Section: 35lb (16kb)
Output Termination	Top mounted 1.5 in aluminum ball
Scope Of Supply	(2) 20ft green/yellow ground leads, 20ft shielded return cable, external interlock plug, operations manual, calibration certificate

PFT Series: Other models are available from 10 kVac - 100 kVac, 1 kVA - 3 kVA

## **Optional Accessories**

**Hand & Foot Safety Switches** 



### Safety Ground Sticks





# **PFT - 401CEF**

0 - 40 kV AC @ 25 mA AC, 1.0 kVA









